

## 1 ADDENDUM #1

ALL CLAUSES SET FORTH IN THE BIDDING DOCUMENTS, CONTRACT DOCUMENTS AND GENERAL REQUIREMENTS OF THE ORIGINAL CONTRACT DOCUMENTS SHALL APPLY TO AND GOVERN THIS WORK. THE ADDENDUM REFERS TO CHANGES AND ADDITIONS TO THE ORIGINAL CONTRACT DOCUMENTS AND IS TO BE READ IN CONJUNCTION WITH THE SAME. ALL OTHER PARTS OF THE ORIGINAL CONTRACT DOCUMENTS ARE TO BE CONSIDERED AS APPLYING TO THE WORK OF THIS CONTRACT WITH THE EXCEPTIONS AND CHANGES AS NOTED BELOW.

### 1.1 DRAWINGS

- .1 Reference Drawing C100 - Demo Plan:
  - .1 Successful Contractor shall be required to relocate one 2400 x 2400 storage shed and one 2400 x 3600 storage shed from the area of the addition to a location on the property to be determined by the school. Distance shall be within 100 m. Place each building on relocated concrete pads set on 150 mm gravel.
  - .2 Successful Contractor shall be required to provide and maintain approximately 100 m of 1.8 m high modular woven wire mesh security fencing around the construction site. Provide a 3 m opening with secure gate where required for access to the site.
- .2 Reference Drawing M100 - New Works Plans, Control Schematic, And Equipment Schedules:
  - .1 **Clarification:** The ERV referenced in the plans is ERV-10, any references to ERV 1 are meant to reference ERV 10.

END OF SECTION