



- LEGEND:**
- NEW VINYL SHEET FLOORING
SEE SPECIFICATIONS FOR COLOUR AND MANUFACTURER.
APPROX. TOTAL AREA = 218 m² (2348 SQ.FT.)
 - EXISTING CARPET TO REMAIN
 - EXISTING WOOD TRIM TO REMAIN
 - EXISTING FLASH COVE TO BE REPLACED APPROX. LENGTH = 122 m (401 ft.)

- GENERAL NOTES:**
1. ALL MEASUREMENTS AND SITE CONDITIONS ARE TO BE CONFIRMED ON SITE BY THE CONTRACTOR. CONTRACTOR IS RESPONSIBLE TO VISIT THE SITE PRIOR TO SUBMITTING A TENDER AND MAKE THEMSELVES FAMILIAR WITH CONDITIONS THAT MAY AFFECT THE WORK.
 2. REMOVAL AND DISPOSAL OF DEMOLISHED MATERIALS TO BE IN ACCORDANCE WITH AUTHORITIES HAVING JURISDICTION.
 3. CONTRACTOR RESPONSIBLE TO MAKE GOOD ALL AREAS AFFECTED UNDER THIS CONTRACT BACK TO ITS ORIGINAL CONDITION. (MATCH EXISTING)
 4. REMOVE UNNECESSARY DEBRIS FROM SITE.
 5. REMOVE EXISTING FLOORING AND BASE AS INDICATED ON DRAWINGS. REPLACE WITH NEW VINYL SHEET FLOORING AND BASE. COLOR TO BE DETERMINED.
 6. DOOR INDICATED ON PLAN TO REMAIN CLOSED. FLOOR SEAM SHALL BE IN FRONT OF DOOR TO ALLOW FOR WORK TO BE COMPLETED WITHOUT OPENING DOOR.
 7. ALL WORK INCLUDING DEMOLITION SHALL MEET CAN/CSA-Z317.13-17 FOR INFECTIO CONTROL (LEVEL "CLASS II").


 Department of
 Transportation and Infrastructure
 PO Box 2000
 Charlottetown
 Prince Edward Island
 Canada C1A 7N8
 Tel 902 368 5100
 Fax 902 569 0590
<http://www.gov.pe.ca/>

ISSUED FOR TENDER

April 13, 2023 by CS

A = Detail #
 BB = Sheet # (Where Detail Required)
 CC = Sheet # (Where Detailed)

Project Title :
Souris Hospital
 Partial Flooring Replacement

Drawing Title :
Flooring Replacement Plan

Scale : 1:200	Design By : CS
Drawn By : MCO, BC	Date : April 13, 2023
Project No.: 2680 - 22045	Drawing # : A1 of 1